










Design & specification considerations  
**Brickwork Bonds and net quantities per m<sup>2</sup>**

	Half brick thick (102mm) assuming half bricks cut on site and best half selected.			One brick thick (215mm)		
	Total	Stretchers	Headers	Total	Stretchers	Headers
<b>Stretcher Bond</b> 	<b>All stretchers 65mm</b>					
	60	60	0	120	120	0
<b>73mm</b> 	<b>All stretchers 65mm</b>					
	54	54	0	108	108	0
<b>Header Bond</b> 	<b>All headers (assuming each brick for a 102mm wall cut on site and best half used.)</b>					
	119	0	119	119	0	119
<b>English Bond</b> 	<b>Alternate courses of headers and stretchers.</b>					
	90	30	60	120	60	60
<b>English Garden Wall</b> Every 4 <sup>th</sup> course (commencing with 3 stretcher rows)  Every 6 <sup>th</sup> course (commencing with 5 stretcher rows)	<b>Stretchers with rows of headers every 4<sup>th</sup> or 6<sup>th</sup> course.</b>					
	73	46	27	128	92	27
<b>Flemish Bond</b> 	<b>Stretchers with rows of headers every 4<sup>th</sup> or 6<sup>th</sup> course.</b>					
	68	50	18	118	100	18
<b>Flemish Bond</b> 	<b>Alternate bricks, header/stretcher, in each course.</b>					
	80	40	40	120	80	40
<b>Flemish Garden Wall</b> 	<b>3 Stretchers to one header in each course.</b>					
	68	51	17	119	102	17
<b>Stack Bond</b> 	<b>All stretchers with perpend directly above the perpend below.</b>					
	60	60	0	Not recommended both sides.		

